BRUHATH BANGALURU MAHANAGARA PALIKE
YELAHANKA ZONE

Name of the work : Detailed Estime for Providing LED Lights at Ward No 04&03.

Budget Head .....

Division No..... Estimate No..... For Rs. **100000.00**

Sl No	SR Page	Description	Unit	Qty	Rate	Amount
1	27/4.36.1	LED Street light. Supply of LED Streetlight with pressure die cast aluminum housing body with optimal heat sink for better thermal dissipation. Diffuser with Injection moulded & is made of polycarbonate material with high transmission index, delivering superior light output. Rated life Burning Hrs. 50000 hr. @ Lumen Maintenance of 70%. CCT > 5500K, IP 66 optical and electrical compartment & impact resistance of complete luminaire > IK08. Power Factor >0.9 with mains Current should not be greater than 0.1A to 0.7A & Surge Protection- Min 4 KV along with Over voltage/Overload, short circuit/ miswiring protection. Compatible for pole mounting with outer dia of 40mm to 50mm. Universal Voltage driver to operate wide voltage range from 100V to 270V 50/60Hz application. Over load & Short circuit protection ensures reliable operation in spite of problem in output side. Compliance to IS 10322/IEC 60598, LM 79 & LM 80 Adherence with RoHS. UL approved MCPCB. Top access street light with single screw to ensure ease of maintenance at the sight site location with minimized minimal tools.LED Light fixture with .....W System Power consumption. LED Efficiency>130lm/w at 1W & Fixture Efficiency >80lm/w with nominal CRI 75+. housing with supplier word mark / name shall be engraved / Embossing on the die cast housing / body part. . Luminaire manufacturer should have in-house facility accredited by NABL/CPRI & any Government certified agency & Design & Development facility certified by ISO 9001:2008. Warranty of 5 Years against any manufacturing defect working under standard electrical conditions as mentioned above should be given by LED source manufacturer. Suitable for A1/A2 Roads as per IS 1944 Part I & Part II. 90 Watts	Nos	3	31250.00	93750.00
2	17.1.2	Supplying and Fixing of.....mm dia class A GI pipe bracket up to 2 mtrs long bent at suitable angle and fixing to this bracket 1x40/2x40 watts fluorescent tube street light fitting of all capacities to GI or CI or rail or RCC pole / wall using suitable clamps, bolts, and nuts and wiring using suitable capacity wires.Using 32mm dia G.I.pipe	N	6	893.00	5358.00

3	2.12.2	Wiring for lighting / power circuit using one of pvc insulated 1100v grade stranded aluminum unsheathed wire single core cable in open or concealed system of wiring as per IS - 694 : 19906sq mm	Nos	90	9.50	855.00
		Mislenious				37.00
		TOTAL				**100000.00**

CERTIFICATE

1. The Place was inspected and work is essential.
2. The Provision made in the estimate is adequate and are necessary.
3. The Work comes in the BBMP limit and is legitimate charges on the Corporation Funds.
4. The rates in the Estimate is based on PWD (Elec) SR of 2014-15 .

Jr/Asst. Engineer (Elec)

Asst. Exe.Engineer (Elec)
yelhanka zone
Bruhat Bangalore Mahanagara Palike

EXECUTIVE ENGINEER (ELEC)
Y ELHANKA ZONE
BRUHAT BANGALORE MAHANAGARA PALIKE

Administrative Sanction for Rs. 1.00 LAKH
RUPEES ONE LAKH ONLY
is accorded under P1517 UPGRADING STREET LIGHTING OF BANGA-LORE MAJOR ROADS
Registered as EE No. ..... Subject to conditions contained in enclosed memo No. BBMP/EE(ELE)/YZ/AS/18/2018-19 Dt 25.09.2018

Executive Engineer

TECHNICALLY SANCTIONED FOR Rs. 1.00 LAKH
Rupees ONE LAKH ONLY
Under P1517 UPGRADING STREET LIGHTING OF BANGALORE
Registered as EE ( ) No. 99
Subject to conditions contained in enclosed memo EE ( ) No. EE/ELE/YZ/AS/18/18-19
Dt. 25.09.2018 Estimate A/ Sanctioned BBMP/EE/ELE/YZ/TS/18/No. 2018-19
Dated 25.09.2018 Rs. 1.00 lac.

Executive Engineer